Minnesota Society of Professional Engineers

Honorable Mention of Seven Wonders of Engineering Award

Minneapolis, MN, 2002



- The new Cast-In-Place Concrete 34 MG Underground Finished Water Reservoir serves the needs of its 500,000 citizens and increases the treated water supply for Minneapolis by 30%.
- This reservoir is considered to be the Largest Concrete Structures in the U.S.A. constructed Without Expansion Joints the potential source of leakage.
- The design performed In-House by MWW Project Engineer, Galina Izraelev, and her extensive day-by-day
 involvement in the construction process as a Project Manager saved the City of Minneapolis over \$1
 Million and prevented the change orders during construction of the concrete superstructure.
- Built-up subgrade between 2 feet and 50 feet over 6 acre site allowed the base of the new reservoir to be build at the same elevation as existing structure thus eliminating the need for a pump station and reducing operational and maintenance cost.
- Steep reinforced earth slopes increased the capacity of the reservoir by 6 MG.
- The earth construction is considered to be the Largest Reinforced Earth Project in Minnesota.





Minnesota Society of Professional Engineers Presented to Minneapolis Water Works

THE HONORABLE MENTION OF SEVEN WONDERS OF ENGINEERING IN MINNESOTA AWARD For Distinguished Engineering Achievement

Underground Finished Water Reservoir Minneapolis, MN, 2002







The massive cast-in-place water containing concrete reservoir (measuring 542'x434'x24'deep) required expansion joints to permit the separate segments of the structure to expand and contract in response to temperature changes during several years of construction without affecting the reservoir structural integrity and serviceability. The potential problem even in the well constructed water reservoirs has been the leakage, and the leaks most likely were to occur through expansion joints.



The reservoir was constructed with control (contraction) joints and expansion joints were eliminated without jeopardizing the structural integrity and reservoir serviceability. The contraction joints were provided at 36 feet intervals in all directions for the entire structure and exact concrete placement sequence requirements were defined for the construction. The alternate sections of bottom slab, walls and top slab no larger ten 36x36 feet have been placed in checkerboard pattern, cured for at least 14 days, and only then the remaining sections have been placed between them. In addition two strips of base slab, including columns, walls and top slab in the longer direction and one strip in the other direction were left uncompleted and were poured only after all other concrete in the entire structure, including top and bottom slabs, exterior and interior walls and columns has been poured.

