

ADDENDUM #2

March 31, 2016

To: Drawings and Specifications Dated March 4, 2016

For: Nicollet Mall Reconstruction Project

CITY PROJECT No. PD9916

S.A.P. No. 141-030-044

MEMO

1. Revisions to Soil Composition table for G2600 fiber rates and lab testing in specification section S-32 91 00.

End Addendum #2



MEMO

Date: March 31, 2016

From: Charles “Chuck” R. Dixon - Agronomist

To: Megan Born - Corner James Field Operations

Cc:

RE: Nicollet Mall Correction of G2600

The table for the G2600 Fiber rates and lab testing in the S-32 91 00 Section was clipped by a page break. The entire table of information is below. The rate and lab values for verification were on the last two lines that did not show up in the issued specification. Let me know if you have any questions.

Property	Test Method	Values
Polypropylene	ASTM D 4101/ Group 1/Class 1/ Grade 2	99.00%
Color		Manila, Green or Black
Moisture Absorption		Nil
Fiber Length		1.5 inch
Specific Gravity	ASTM D792	0.91 g/cm3
Tensile Strength	ASTM D 2256	40,000 psi
Tensile Elongation	ASTM D2256	20.00%
Young's Modulus	ASTM D2101	600,000 psi
Denier		2600 Fibrilated
Estimated Application Rate		7 lb per ton Mix
Percent Fiber Dry Weight	Turf & Soil Diagnostics	0.3% to 0.4%