

# 33<sup>rd</sup> St E Reconstruction

June 25, 2018



## Project Fact Sheet

The City of Minneapolis proposes to reconstruct 33<sup>rd</sup> Street East between Hiawatha Ave S and Minnehaha Ave S. The proposed 0.2 mile long project is scheduled to occur over the 2019 construction season and will consist of improvements to the roadway, sidewalk, and utilities. City staff is currently in the preliminary stages of planning and design for the project, which will be accompanied by community outreach activities that will help inform and guide design concepts.

### PROJECT AREA MAP



### PURPOSE

The scope of the project will encompass the entire right-of-way and include full removal of the existing street, subgrade correction, new pavement, curb and gutter, driveways, sidewalks and utility work as needed. The project will coordinate with the railroad to improve conditions at the rail crossing.

### EXISTING CONDITIONS

The existing right of way is 60 feet wide and the street width is 44 feet from curb to curb. Existing sidewalks range from 6.5 feet to 8 feet in width with some obstructions within the pedestrian through walk. Pedestrian ramps are generally not ADA compliant and there is currently no boulevard present. The railroad is active with approximately 16 rail crossings per day. The pavement condition was rated in very poor condition.



### SCHEDULE



### CONTACT

If you would like to learn more about the proposed reconstruction, request additional information, or share your ideas please visit the project website or contact the project team using the contact information provided below.

Forrest Hardy  
Transportation Planning & Programming  
[Forrest.Hardy@minneapolismn.gov](mailto:Forrest.Hardy@minneapolismn.gov)  
612-673-5951

Debra Jacobs  
Transportation Engineering & Design  
[Debra.Jacobs@minneapolismn.gov](mailto:Debra.Jacobs@minneapolismn.gov)  
612-673-2463

Project Website: <http://www.minneapolismn.gov/cip/33rd-and-35th-streets>